



### Completion Details:

- There is no completion as such.
- Water is pumped down the 13-3/8" casing and the 9-5/8" liner.
- The reason for the 13-3/8" casing is to provide the ability to run an ESP in case it's required to test the productivity of the well.
- There is 150m of 7" tubing hanging from the wellhead to inject the water into the well.